

BERECHNUNG UMBAUTEN RAUM / KUBISCHE BERECHNUNG NACH SIA 1161 UMBAUTEN RAUM.01 UNTERGESCHOSS

UG Technik/Waschen	7.28	x	3.80	=	27.67	x	2.74	=	75.80 m3
UG Keller	3.77	x	4.26	=	16.06	x	2.74	=	44.00 m3
UG Basteln	3.51	x	6.54	=	22.96	x	2.91	=	66.81 m3
UG Vorplatz	3.77	x	2.28	=	8.60	x	2.91	=	25.02 m3
Bodenzuschlag				=	8.60	x	1.00	=	8.60 m3

.02 ERDGESCHOSS

EG Haus	7.36	x	10.50	=	77.28	x	2.74	=	211.75 m3
EG Zugang Reduit	3.76	x	2.50	=	9.40	x	2.78	=	26.13 m3
Flachdachzuschlag Reduit				=	9.40	x	0.50	=	4.70 m3
Zugangstreppe	2.30	x	2.10	=	4.83	x	1.35	=	6.52 m3
Zugangstreppe	2.10	x	2.50	=	5.25	x	1.35	=	7.09 m3
Pergola	3.65	x	3.00	=	10.95	x	2.65	=	29.01 m3
Bodenzuschlag				=	10.95	x	1.00	=	10.95 m3
Flachdachzuschlag n.beg. zur Hälfte gemessen				=	10.95	x	0.50	=	5.47 m3 -22.72 m3

.03 OBERGESCHOSS

OG	7.36	x	10.50	=	77.28	x	2.74	=	211.75 m3
Flachdachzuschlag beg.1.50	1.50	x	6.37	=	9.55	x	1.00	=	9.55 m3
Flachdachzuschlag beg.7.36	7.36	x	4.13	=	30.40	x	1.00	=	30.40 m3

.03 DACHGESCHOSS

DG	7.36	x	6.37	=	46.88	x	2.94	=	137.83 m3
Flachdachzuschlag n.beg.				=	46.88	x	0.50	=	23.44 m3
Vordächer	7.36	x	1.47	=	10.82	x	1.00	=	10.82 m3
Vordächer	7.36	x	0.50	=	5.41	x	1.00	=	5.41 m3
Vordächer	1.50	x	6.37	=	9.55	x	1.00	=	9.55 m3

SUBTOTAL 937.88 m3

Rundbetrag - 0.88 m3

TOTAL - UMBAUTER RAUM / HAUS 937.00 m32 BRUTTOGESCHOSSFLÄCHE

DG	5.86	x	6.37	=	37.33 m2
OG	7.36	x	10.50	=	77.28 m2
EG	7.36	x	10.50	=	77.28 m2
UG				=	0.00 m2

TOTAL – BRUTTOGESCHOSSFLÄCHE / HAUS 191.89 m2